

TEST REPORT

CLIENT:

CLILINT.			-
Company:	American Syn-Turf, Inc.	Report Number:	79614D
Address:	5960 Inglewood Dr, Ste 150	Lab Test Number:	3174-2619
	Pleasanton, CA 94588	Test Completion Date:	2/10/2020
		Report Date:	2/13/2020
Requested by:	Greg Weitz	Page:	1 of 1

TEST MATERIAL:

Material Type:	Synthetic Turf Date Received: 1/29/2020					
Material Condition:	EXCELLENT:	XXX	GOOD:	POOR:	REJECTED:	
Product ID:	Superscape Series					
Infill System:	1.0 lbs/ft ² 20/40 Silic	a Sand				

TESTING METHODS REQUESTED:

Testing Services Inc. was instructed by the client to test for the following			
Standard:	ASTM F1551	Test Method:	Standard Test Methods for Comprehensive Characterization of Synthetic Turf Playing Surfaces and
			Materials: Suffix-DIN 18-035, Part 6: Water Permeability of Synthetic Turf Systems and Permeable Bases

SAMPLING PLAN:

Sampling Date:	1/29/2020		
 Specimen sample 	pling is performed in the sampling department at TSI.		
 The sampling si 	The sampling size of specimens is determined by the test method requirements.		
 In the event a s 	specific sampling size is not called for, a determination will be made based on previous testing experience, and approved for use by an authorized manager.		
 All samples are 	subjected to the outside environmental conditions of temperature and relative humidly.		

Sample requiring pre-determined exposure to specified environmental conditions based on a specific test method, take place in the departments in which they are tested

PROCEDURE:

This test method determines the rainfall drainage capacity (permeability) of the playing surface. Test data values represent drainage rates vertically thru the turf with above listed infill, and do not take into account the percolation properties of a pad and/or an underlying sub base. Three specimens, 11.5" diameter, were cut from the 15" turf roll, side-center-side manner. Each turf specimen was securely fastened to the permeability tube using mechanical flanges, ensuring vertical water flow thru the product. The infill system was then installed. Water was pumped into the tube faster than could exit, until the water level reached 6". The water source was shut off, allowing the accumulated 6" water level to recede. The recede was timed via stopwatch until the water level exited the turf. The flow time was recorded in seconds. This procedure was repeated a total of 4 times where, the first pass was for conditioning, with passes 2,3,4 used for averaging. This process was repeated on the remaining specimens.

DEVIATION FROM TEST METHOD:

State reason for any Deviation from, Additions to, or Exclusions From Test Method.
None

TEST SUMMARY:

Specimen #	Drainage (Seconds)	gal/min/yd ²	Rainfall Capacity (inches/hour)
1	44.7	45.2	138.5
2	41.7	48.5	148.7
3	43.8	46.1	141.5
Average	43.4	46.6	142.8

Uncertainty:

We undertake all assignments for our clients on a best effort basis. Our findings and judgments are based on the information to us using the latest test methods available.

TSI can only ensure the test results for the specific items tested.

Unless otherwise noted in the deviations sections of this report, all tests are performed in compliance with stated test method.

Test Report Approval:

	Erle Miles, III, Lab Director Testing Services (TSI) LLC
TSi Accreditation:	TSi is a certified independent testing laboratory by the Synthetic Turf Council



OUR LETTERS AND REPORTS APPLY ONLY TO THE SAMPLE TESTED AND ARE NOT NECESSARILY INDICATIVE OF THE QUALITIES OF APPARENTLY IDENTICAL OR SIMILAR PRODUCTS. THESE LETTERS AND REPORTS ARE FOR THE USE ONLY OF THE CLIENT TO WHOM THEY ARE ADDRESSED AND THEIR COMMUNICATION TO ANY OTHERS OR THE USE OF THE NAME TESTING SERVICES, INC. MUST RECEIVE OUR PRIOR WRITTEN APPROVAL. OUR REPORTS, LETTERS, NAME, SEALS, OR INSIGNIA ARE NOT UNDER ANY CIRCUMSTANCES TO BE USED IN ADVERTISING TO THE GENERAL PUBLIC.

817 Showalter Ave Dalton, GA 30722 (706) 226-1400 tsioffice@optilink.us